



As-Built Requirements

08/08/18

As-Built the Following:

Building Layout with dimensions

Paving/Grading:

Layout

Elevations at all High points and low Points

Elevations at all curbs

Elevations at all property lines, minimum 50 foot on center

Storm Sewer:

Lengths

Rim Elevations

Invert Elevations

Dimensions from Property Lines or other permanent field identifiable objects

Slope

Sanitary Sewer:

Lengths

Rim Elevations

Invert Elevations

Dimensions from Property Lines or other permanent field identifiable objects

Slope

Watermain:

Lengths

Rim Elevations

Hydrants - Finish Grade Elevation

Dimensions from Property Lines or other permanent field identifiable objects

Sidewalks:

Layout

Elevations

Retention Basins:

Elevations

Contours

Drainage district map

Storm Sewer Calculations and Profiles (updated if elevations and slope are different from design)

Include all easements with Liber and Page if recorded.

Include PSP/SPR and EG Number

Final submission to be on a Reproducible Mylar, 3 Mil, 24" x 36"

*Paper may be submitted for first review prior to acceptance

*Do Not Fold or Staple

*All corrections must be done using permanent ink

*A pdf compatible file may be submitted in addition to the Reproducible Mylar

Do Not submit:

Soil Erosion sheet

General Notes sheet

Standard Detail sheets

Cover Sheet

** Any shading should be removed and/or kept to a minimum density for future scanning purposes